DEUTSCHES SPRING- UND DRESSURDERBY · HAMBURG

HAMBURG DERBY 2026

EVENT DATES	PROJECT PERIOD	LOCATION	PROJECT MANAGER
12 – 17 May 2026	**04 – 18 May 2026**	**Hamburg, Germany**	**Thibaut Bollen**

MAIN ARENA 01

Screen A

DIMENSIONS	8 m × 4,5 m
SURFACE AREA	36 m²
TOTAL POWER	21.600 W
WEIGHT	1.100 kg
CONSTRUCTION	Stacked on Layher scaffolding
MACHINERY	Rotating Telehandler
POWER CONNECTION	63A

Screen B

DIMENSIONS	7 m × 4 m
SURFACE AREA	28 m²
TOTAL POWER	16.800 W
WEIGHT	840 kg
CONSTRUCTION	Stacked on Layher scaffolding
MACHINERY	Telehandler
POWER CONNECTION	32A

LED Scoring Display

CONFIGURATION	4 × LED panel — horizontal strip
POSITION	Above judges / timing post
POWER CONNECTION	32A
POWER NOTE	For LED processors & LED scoring

EXHIBITION AREA 02

LED Screen — Food Court

DIMENSIONS	4 m × 2 m
SURFACE AREA	8 m²
TOTAL POWER	4.800 W
WEIGHT	240 kg
CONSTRUCTION	Hanging — suspended from circular truss
POWER CONNECTION	2 × 16A

LED Totem — Kids Play Area

SURFACE AREA	8 m²
TOTAL POWER	4.800 W
POWER CONNECTION	2 × 16A

DRESSAGE ARENA 03

LED Screen

DIMENSIONS	9 m × 5 m
SURFACE AREA	45 m²
TOTAL POWER	27.000 W
WEIGHT	1.350 kg
CONSTRUCTION	Hanging — truss with side banners (2 × 5m × 5m)
MACHINERY	Telehandler + Cherrypicker
POWER CONNECTION	63A

LED SPORTPERIMETER 04

SECTION	PANELS	RESOLUTION	LENGTH
Bottom Grandstand	72	13824 × 144 px	**92,16 m**
Top Grandstand	54	10368 × 144 px	**69,12 m**
VIP	84	16128 × 144 px	**107,52 m**
Public seating area	102	19584 × 144 px	**130,56 m**
Tractor entrance	8	1536 × 144 px	**10,24 m**

SECTION 05

PLANNING

DATE	DAY	ACTIVITIES
04 / 05	Monday	Arrival Truck 1
06 / 05	Wednesday	Arrival Truck 2 + crew
07 / 05	Thursday	Start build-up Unloading of trucks Build dressage screen Start building LED boarding
08 / 05	Friday	Build LED boarding Start build Big Screen 1 — Main Arena
09 / 05	Saturday	Finish off big screen 1 Build big screen 2
10 / 05	Sunday	Finish off big screens Build screen — Food Court Place screen — Kids area
11 / 05	Monday	Last truck + 120 m LED boarding arrives LED perimeter finished by 4:00 PM
12 / 05	Tuesday	Fully operational · Build-up team leaves 🏆 EVENT Day 1 · Permanence
13 / 05	Wednesday	🏆 EVENT Day 2 · Permanence
14 / 05	Thursday	🏆 EVENT Day 3 · Permanence
15 / 05	Friday	🏆 EVENT Day 4 · Permanence
16 / 05	Saturday	🏆 EVENT Day 5 · Permanence
17 / 05	Sunday	🏆 EVENT Day 6 · Permanence 17:00 — Breakdown team arrives Partial dismantling of LED sportperimeter Dismantling of LED screen — Dressage Arena
18 / 05	Monday	Full dismantling
19 / 05	Tuesday	Departure of trucks and breakdown team

Transport · Build-up · Operational · Event · Breakdown

SECTION 06

MACHINERY REQUIRED

1 × Gator (UTV)

BUILD-UP & BREAKDOWN — FULL DURATION

Two units needed for both build-up and breakdown to move materials around the site.

2 × Flat Trailer (Bockmann or equiv.)

BUILD-UP & BREAKDOWN — FULL DURATION

To transport LED boarding crates around the arena. The stronger the better — Bockmann trailers are ideal.

Confirm availability in advance. This has been an issue in previous years — please confirm on time.

Forklift — 3T Articulated

BUILD-UP & BREAKDOWN — FULL DURATION

Preferably articulated, 3 tonnes. Required for the full duration of build-up and breakdown.

Cherrypicker / Scissor Lift (offroad)

09–10 / 05 (BUILD-UP) · 18 / 05 (BREAKDOWN)

Offroad tires required. Sat & Sun 09–10 May for build-up, and 18 May for breakdown.

Rotating Telescoping Handler

08–11 / 05 (BUILD-UP) · 17–18 / 05 (BREAKDOWN)

Fri–Mon build-up + Sun–Mon breakdown. For Big Screen Main Arena and Dressage Arena screen.

SECTION 07

HOTEL PLANNING *(PROVISIONAL)*

NAME	ROLE	HOTEL NIGHTS	CONTACT
Thibaut Bollen	Project Manager	**06/05 – 19/05**	+32 498 10 63 63
Gaëtan Tulleneers	LED Technician	**06/05 – 19/05**	+32 470 67 81 71
Arno Boone	LED Technician	**06/05 – 19/05**	+32 472 40 00 47
Tim Boon	Truck Driver	**06/05 – 12/05 & 17–19/05**	+32 468 20 09 82
Jules Ickmans	LED Technician	**06/05 – 11/05**	+32 487 43 42 23
Thomas Tielemans	LED Technician	**06/05 – 12/05 & 17–19/05**	+32 471 73 60 11
Joost Rubberecht	Technician — Breakdown	**17–19/05**	+32 479 28 04 84
Jenthe van Maldergem	LED Technician	**17–19/05**	+32 483 37 14 95